

Detroit Apartment Area Schedule May 2015							
Level	Unit Number	Stage ²	No. of Beds	No. of Bathrooms	Internal Area	External Area	Total Area
One	Unit 101	2	3	1	74.1m ²	4.6m ²	78.7m²
	Unit 102	2	2	2	63.3m ²	6.4m ²	69.7m²
	Unit 103	2	2	1	69.4m ²	4.6m ²	74m²
	Unit 104	2	3	1	64.8m ²	5.5m ²	70.3m²
	Unit 105	2	3	1	67.8m ²	5.2m ²	73.0m²
	Unit 106	1	2	1	54.0m ²	4.5m ²	58.5m²
	Unit 107	1	2	1	54.0m ²	4.5m ²	58.5m²
	Unit 108	1	2	1	55.7m ²	4.8m ²	60.5m²
	Unit 109	1	3	1	70.8m ²	8.6m ²	79.4m²
	Unit 110	1	3	2	74.7m ²	9.7m ²	84.4m²
	Unit 111	2	3	1	70.7m ²	5.3m ²	76.0m²
	Unit 112	2	2	1	53.2m ²	4.3m ²	57.5m²
	Unit 113	2	3	2	67.4m ²	7.3m ²	74.7m²
Two	Unit 201	2	3	1	74.1m ²	4.6m ²	78.7m²
	Unit 202	2	2	2	63.3m ²	6.4m ²	69.7m²
	Unit 203	2	3	1	67.9m ²	7.9m ²	75.8m²
	Unit 204	2	2	1	64.8m ²	5.5m ²	70.3m²
	Unit 205	2	3	1	67.8m ²	5.2m ²	73.0m²
	Unit 206	1	2	1	54.0m ²	4.6m ²	58.6m²
	Unit 207	1	2	1	54.0m ²	6.6m ²	60.6m²
	Unit 208	1	2	1	55.7m ²	4.7m ²	60.4m²
	Unit 209	1	3	1	70.8m ²	4.1m ²	74.9m²
	Unit 210	1	3	2	74.7m ²	4.9m ²	79.6m²
	Unit 211	2	3	1	72.7m ²	4.8m ²	77.5m²
	Unit 212	2	3	2	77.4m ²	3.5m ²	80.9m²
	Unit 213	2	3	2	83.8m ²	5.7m ²	89.5m²
	Unit 214	2	2	2	66.4m ²	6.0m ²	72.4m²
Three	Unit 301	2	3	1	74.1m ²	4.6m ²	78.7m²
	Unit 302	2	2	2	63.3m ²	6.4m ²	69.7m²
	Unit 303	2	3	1	67.9m ²	7.9m ²	75.8m²
	Unit 304	2	2	1	64.8m ²	5.5m ²	70.3m²
	Unit 305	2	3	1	67.8m ²	5.2m ²	73.0m²
	Unit 306	1	2	1	54.0m ²	4.6m ²	58.6m²
	Unit 307	1	2	1	54.0m ²	6.6m ²	60.6m²
	Unit 308	1	2	1	55.7m ²	4.7m ²	60.4m²
	Unit 309	1	3	1	70.8m ²	4.1m ²	74.9m²
	Unit 310	1	3	2	74.7m ²	4.9m ²	79.6m²
	Unit 311	2	3	1	72.7m ²	4.8m ²	77.5m²
	Unit 312	2	3	2	77.4m ²	3.5m ²	80.9m²
	Unit 313	2	3	2	83.8m ²	5.7m ²	89.5m²
	Unit 314	2	2	2	66.4m ²	6.0m ²	72.4m²

NOTES: 1. Areas are approximate and are as measured on the architectural drawings. Final constructed areas can be subject to minor variation as a result of normal constructional anomalies. If required, a final "as-built" survey can be undertaken following completion. Areas are measured to inside faces of external walls and centreline of intertenancy walls.

2. Stage 1 was completed in August 2014. Stage 2 is on program to achieve practical completion in August 2015.